

ARKANSAS DEPARTMENT OF TRANSPORTATION
SUPPLEMENTAL SPECIFICATION
DESIGN AND QUALITY CONTROL OF ASPHALT MIXTURES

Division 400 of the Standard Specifications for Highway Construction, Edition of 2014, is hereby amended as follows:

Section 404, QUALITY CONTROL OF ASPHALT MIXTURES, is hereby modified as follows:

The third paragraph **Subsection 404.04** is hereby deleted and the following substituted therefore:

The accepted mix design shall be field verified by the Contractor at the start of mix production or after an interruption of more than 120 calendar days. The asphalt mixture shall be verified by testing mix that has been produced through the plant using the aggregate proportions shown on the accepted mix design. Production of Department approved mix designs for placement on non-ARDOT projects may be used for mix verification. The Contractor shall notify the Engineer sufficiently in advance for Department personnel to witness all testing of this production and shall provide copies of all test results to the Department.

Section 410, Construction Requirements and Acceptance of Asphalt Concrete Plant Mix Courses is hereby modified as follows:

The first and second sentence of **Subsection 410.09, Acceptance of the Payment and Adjustments in Payment**, is hereby deleted and the following is substituted therefore:

- (a) General. The accepted mix design shall be verified by the Contractor at the start of mix production for that design or after an interruption of more than 120 calendar days. A maximum of 200 tons (200 metric tons) of materials may be placed on the roadway during the verification process.

Section 411, Asphalt Concrete Plant Mix is hereby modified as follows:

The third sentence of Subsection 411.05 (B), Acceptance is hereby amended and the following is substituted therefore:

- (b) Acceptance. The accepted mix design shall be field verified by the Contractor at the start of mix production or after an interruption of more than 120 calendar days.