




DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
							JOB NO.	
							TYPE E APPROACH SLAB	55040E

Notes:
The surface finish for Approach Slabs shall match that used on the bridge deck.
All longitudinal lines within the limits of horizontal curves shall be on curves concentric to C.L. Bridge. Adjustment to longitudinal bar lengths may be required. Transverse reinforcing shall be placed on radial lines to C.L. Bridge.

BENDING DIAGRAMS



PLAN - SKEWED APPROACH SLAB WITH APPROACH GUTTERS
1/4" = 1'-0"



PLAN - SQUARE APPROACH SLAB
1/4" = 1'-0"


BAR LIST

(Square & Skewed Approach Slabs)

Slab Width	Square		Skewed		
	Mark	No. Req'd.	Length	No. Req'd.	Length
20'-0"	S401	18	19'-8"	22	19'-8"
	S402	—	—	20	9'-10"
	S403	28	3'-0"	*	3'-0"
	S404	20	7'-2"	20	7'-2"
	S4...	—	—	1 Ea.	19.7' - 1.25'/(tan skew angle) to 2'-0" Min.
22'-0"	S401	18	21'-8"	22	21'-8"
	S402	—	—	22	9'-10"
	S403	28	3'-0"	*	3'-0"
	S404	22	7'-2"	22	7'-2"
	S4...	—	—	1 Ea.	21.7' - 1.25'/(tan skew angle) to 2'-0" Min.
24'-0"	S401	18	23'-8"	22	23'-8"
	S402	—	—	24	9'-10"
	S403	28	3'-0"	*	3'-0"
	S404	24	7'-2"	24	7'-2"
	S4...	—	—	1 Ea.	23.7' - 1.25'/(tan skew angle) to 2'-0" Min.
24'-0"	S501	48	19'-8"	—	—
	S501 - S548	—	—	1 Ea.	19.6' + 0.25' (tan skew angle) to 19.6' + 23.75' (tan skew angle)
	S401	18	35'-8"	22	35'-8"
	S402	—	—	36	9'-10"
	S403	28	3'-0"	*	3'-0"
36'-0"	S404	36	7'-2"	36	7'-2"
	S4...	—	—	1 Ea.	35.7' - 1.25'/(tan skew angle) to 2'-0" Min.
	S501	72	19'-8"	—	—
	S501 - S572	—	—	1 Ea.	19.6' + 0.25' (tan skew angle) to 19.6' + 35.75' (tan skew angle)


*Varies with skew angle

1/2" x 1" Poured Jt. Sealer (Type 3 or 4) per Subsection 501.02(h)(2) Backer rod is not required.




DETAILS OF LONGITUDINAL CONSTRUCTION JOINT
1" = 1'-0"

1/2" x 1" Poured Jt. Sealer (Type 3 or 4) per Subsection 501.02(h)(2) Backer rod is not required.




SECTION A-A
N.T.S.




SECTION B-B
AT ASPHALT APPROACH PAVEMENT
N.T.S.

Seal expansion joint according to details shown on Std. Dwg. CPTJ-6A



SECTION B-B
AT CONCRETE APPROACH PAVEMENT
N.T.S.



SECTION X-X
SQUARE APPROACH SLAB SHOWN
1/4" = 1'-0"

SECTION Y-Y
N.T.S.

TABLE OF QUANTITIES FOR ONE SQUARE APPROACH SLAB

(FOR INFORMATION ONLY)

Slab Width	Reinforcing Steel (Lbs.)	Concrete (Cu. Yds.)
20'-0"	1210	15.60
22'-0"	1325	17.20
24'-0"	1440	18.70
36'-0"	2135	28.10

GENERAL NOTES
This drawing is for use with Reinforced Concrete Slab Spans in Seismic Performance Zones 2, 3 & 4 and for the maximum skew angles shown below:

- 20'-0" Slab Width: Maximum Skew Angle = 45°
- 22'-0" Slab Width: Maximum Skew Angle = 45°
- 24'-0" Slab Width: Maximum Skew Angle = 40°
- 36'-0" Slab Width: Maximum Skew Angle = 30°

All concrete shall be Class S (AE) with a minimum 28 day compressive strength f'c = 4,000 psi and shall be poured in the dry.

All reinforcing steel shall be Grade 60 (yield strength = 60,000 psi) conforming to AASHTO M 31 or M 322, Type A, with mill test reports.

Approach Slabs will be measured and paid for in accordance with Section 504.

STANDARD DETAILS FOR TYPE E APPROACH SLAB
ARKANSAS STATE HIGHWAY COMMISSION

LITTLE ROCK, ARK.

DRAWN BY: A.M.S. DATE: 2/27/2014 FILENAME: b55040e.dgn
CHECKED BY: K.W.Y. DATE: 2/27/2014 SCALE: AS SHOWN
DESIGNED BY: STD. DATE:

DRAWING NO. 55040E