

QUANTITY	UNIT	ITEM	HILL BROS. CONST. & ENGRNG. CO., INC.	MCGEORGE CONTRACTING CO., INC.	GILBERT CENTRAL CORP	AVG. OF LOW BIDS
1.00	L.S.	REMV.EXIST.BR.STR.(SITE 1)	60,000.00	8,000.00	50,000.00	39,333.33
567.00	CUYD	UNCLASS.EXCAV.FOR STRS-BR	50.00	48.00	150.00	82.67
261.70	CUYD	CLASS S CONCRETE-BRIDGE	650.00	460.00	710.00	606.67
227.60	CUYD	CLASS S(AE) CONCRETE-BRIDGE	650.00	440.00	800.00	630.00
42.30	GAL	CLASS 1 PROTECT.SURF.TREATMENT	40.00	55.00	60.00	51.67
30,420.00	LB	REINF.STEEL-BRIDGE (GR 60)	0.75	0.78	1.15	0.89
65,640.00	LB	EPOXY COAT.REINF.STEEL-GR 60	0.80	0.85	0.80	0.82
508.00	LF	STEEL PILING (HP 12X53)	55.00	51.00	90.00	65.33
121,870.00	LB	STR.ST.BM.SPANS(M270-GR50W)	1.60	1.46	1.75	1.60
17,462.00	CUIN	ELASTOMERIC BEARINGS	1.60	1.20	2.00	1.60
181.00	LF	PREFORMED JOINT SEAL	80.00	45.00	50.00	58.33
1.00	EACH	BRIDGE NAME PLATE (TYPE D)	800.00	700.00	500.00	666.67
1,870.00	SQYD	FILTER BLANKET	3.25	2.80	3.00	3.02
935.00	CUYD	DUMPED RIPRAP	30.00	34.14	46.00	36.71
TOTAL AMOUNT BID FOR JOB			\$17,420,112.07	\$17,508,776.63	\$27,677,258.74	
TOTAL AMOUNT BID FOR BRIDGE			\$783,692.70	\$608,384.60	\$945,056.50	

BRIDGE ID	LENGTH	WIDTH	AREA (OUT-OUT)	NEW BRIDGE DESCRIPTION	EXISTING BRIDGE DESCRIPTION
07048	113.52	78.17	8,873.55	1A	1B
		A =	8,873.55		

1A 111'-0" CONT COMPOSITE W-BEAM UNIT (37'-37'-37') ON MULTI-COLUMN INT BENTS W/SPREAD FOOTING; STUB END BENTS ON STEEL H-PILING.

1B #02941 - 31'-6" W X 100' L; CONSISTS OF 4- 25' REINFORCED CONCRETE SLAB SPANS ON TWO-COLUMN INTERIOR BENTS & 5-PILE END BENTS.

OUT TO OUT COST (\$/SF)=	\$783,692.70 /A = \$88.32	* FHWA COST (\$/SF)=	\$689,565.20 /A = \$77.71
LESS REMOVAL / TEMP. BR.	(\$/SF) = \$6.76	EXISTING BR. REMOVAL (\$/SF)	= \$19.05
NET COST (\$/SF)	= \$81.56	* DEDUCT REMOVAL, TEMP. BR., RIPRAP, & FILTER BLANKET COSTS	

FUNCTION CLASS - PRINCIPAL ARTERIAL - OTHER
 ON (02)

DESIGN SECTION - CJF