

QUANTITY	UNIT	ITEM	C. WATTS & SONS CONST. CO., INC.	EUTAW CONSTRUCTION CO., INC.	MCGEORGE CONTRACTING CO., INC.	AVG. OF LOW BIDS
402.00	CUYD	UNCLASS.EXCAV.FOR STRS-BR	108.00	49.00	50.00	69.00
352.20	CUYD	CLASS S CONCRETE - BRIDGE	540.00	590.00	600.00	576.67
426.40	CUYD	CLASS S(AE) CONCRETE - BRIDGE	540.00	610.00	600.00	583.33
1,343.00	LF	PRESTESS CONC GIRDERS (TY BT-72)	230.00	195.00	200.00	208.33
28.80	GAL	CLASS 1 PROTECT.SURF.TREATMENT	70.00	25.00	25.00	40.00
121,650.00	LB	REINF.STEEL-BRIDGE (GR 60)	0.66	1.00	0.90	0.85
428.00	LF	STEEL PILING (HP 12X53)	59.00	40.00	40.00	46.33
8,000.00	LB	STR.ST.BM.SPANS (M270-GR50)	10.00	5.05	5.00	6.68
2.20	TON	PAINTING STRUCTURAL STEEL	1,050.00	510.00	500.00	686.67
18,624.00	CUIN	ELASTOMERIC BEARINGS	1.77	1.50	1.50	1.59
74.00	LF	ARM. JT W/NEOPRENE STRIP SEAL	150.00	200.00	200.00	183.33
1.00	EACH	BRIDGE NAME PLATE (TYPE D)	1,600.00	1,500.00	1,200.00	1,433.33
74.00	CUYD	CONCRETE RIPRAP	500.00	308.00	300.00	369.33
TOTAL AMOUNT BID FOR JOB			\$11,294,748.14	\$12,071,526.66	\$13,480,977.06	
TOTAL AMOUNT BID FOR BRIDGE			\$1,045,281.48	\$997,525.00	\$990,421.00	

BRIDGE ID	LENGTH	WIDTH	AREA (OUT-OUT)	NEW BRIDGE DESCRIPTION	EXISTING BRIDGE DESCRIPTION
07080	342.76	31.17	10,682.71	1A	NA
		A =	10,682.71		

1A 340'- CONT COMP PRESTRESSED CONC GIRDER UNIT (54'-120'-120'-46') ON MULTI-COL INT BENTS W/SPREAD FOOTINGS & STUB END BENTS W/STEEL PILING.

1B NA

OUT TO OUT COST (\$/SF)=	\$1,045,281.48	/A = \$97.85	* FHWA COST (\$/SF)=	\$1,008,281.48	/A = \$94.39
LESS REMOVAL / TEMP. BR.	(\$/SF)	= NA	EXISTING BR. REMOVAL (\$/SF)	= NA	
NET COST (\$/SF)		= \$97.85	* DEDUCT REMOVAL, TEMP. BR., RIPRAP, & FILTER BLANKET COSTS		

FUNCTION CLASS - PRINCIPAL ARTERIAL - OTHER
 ON (02)

DESIGN SECTION - CJF