

QUANTITY	UNIT	ITEM	TOM LINDSEY CONTRACTOR, INC.	MANHATTAN ROAD & BRIDGE CO.	MOBLEY CONTRACTORS, INC.	AVG. OF LOW BIDS
240.00	LF	7' STEEL CHAIN LINK FENCE	80.00	55.00	63.00	66.00
35.00	CUYD	UNCLASS.EXCAV.FOR STRS-BR	100.00	40.00	50.69	63.56
131.70	CUYD	CLASS S CONCRETE - BRIDGE	525.00	860.00	1,181.47	855.49
331.70	CUYD	CLASS S(AE) CONCRETE - BRIDGE	625.00	620.00	595.44	613.48
23.30	GAL	CLASS 1 PROTECT.SURF.TREATMENT	75.00	46.00	126.59	82.53
18,020.00	LB	REINF.STEEL-BRIDGE (GR 60)	0.80	1.20	0.90	0.97
62,290.00	LB	EPOXY COAT.REINF.STEEL-GR 60	0.95	1.20	0.90	1.02
365.00	LF	STEEL PILING (HP 12X53)	100.00	55.00	65.51	73.50
54.00	LF	CORING DRILLED SHAFT	183.75	120.00	301.33	201.69
108.00	LF	DRILLED SHAFT (54" DIAMETER)	1,034.25	680.00	501.81	738.69
4.00	EACH	CROSSHOLE SONIC LOGGING (54" DI	4,200.00	1,250.00	4,119.60	3,189.87
226.00	LF	METAL BRIDGE RAILING (TYPE H)	69.00	85.00	84.96	79.65
4.00	EACH	TRANSITIONAL APPROACH RAILING	4,250.00	4,500.00	5,339.34	4,696.45
236,200.00	LB	STR.ST.BM.SPANS(M270-GR50W)	1.55	2.50	1.53	1.86
10,305.00	CUIN	ELASTOMERIC BEARINGS	2.15	3.15	2.30	2.53
82.00	LF	PREFORMED JOINT SEAL	85.00	65.00	87.53	79.18
1.00	EACH	BRIDGE NAME PLATE (TYPE C)	100.00	590.00	954.00	548.00
220.00	CUYD	CONCRETE RIPRAP	425.00	475.00	414.51	438.17
TOTAL AMOUNT BID FOR JOB			\$2,682,493.73	\$2,750,000.31	\$2,782,619.17	
TOTAL AMOUNT BID FOR BRIDGE			\$1,070,845.25	\$1,306,545.55	\$1,081,056.07	

BRIDGE ID	LENGTH	WIDTH	AREA (OUT-OUT)	NEW BRIDGE DESCRIPTION	EXISTING BRIDGE DESCRIPTION
04868	224.16	40.17	9,003.62	1A	NA
		A =	9,003.62		

1A 222' - CONT COMP STEEL W-BEAM UNIT (66'-90'-66') ON MULTI-COL INT BENTS ON DRILLED SHAFTS & STEEL PILE END BENTS.

1B

OUT TO OUT COST (\$/SF)=	\$1,070,845.25	/A = \$118.94	* FHWA COST (\$/SF)=	\$960,345.25	/A = \$106.67
LESS REMOVAL / TEMP. BR.	(\$/SF)	= NA	EXISTING BR. REMOVAL (\$/SF)	=	NA
NET COST (\$/SF)	=	\$118.94	* DEDUCT REMOVAL, TEMP. BR., RIPRAP, & FILTER BLANKET COSTS		

FUNCTION CLASS - MINOR ARTERIAL  
 ON (06)

DESIGN SECTION - CJF