

QUANTITY	UNIT	ITEM	C. WATTS & SONS CONST. CO., INC.	FORSGREN, INC.	DEAN CROWDER CONST, INC.	AVG. OF LOW BIDS
1.00	L.S.	REMV.EXIST.BR.STR. (SITE 1)	56,000.00	53,000.00	177,984.00	95,661.33
76.00	CUYD	UNCLASS.EXCAV.FOR STRS-BR	94.40	89.30	91.80	91.83
315.90	CUYD	CLASS S CONCRETE - BRIDGE	584.00	551.00	567.00	567.33
876.30	CUYD	CLASS S(AE) CONCRETE - BRIDGE	499.00	446.00	459.00	468.00
2,760.00	LF	PRESTRESSED CONC. GIRDERS-III	173.00	164.00	189.00	175.33
64.00	GAL	CLASS 1 PROTECT.SURF.TREATMENT	80.00	75.60	77.75	77.78
53,270.00	LB	REINF.STEEL-BRIDGE (GR 60)	0.84	0.79	0.80	0.81
175,180.00	LB	EPOXY COAT.REINF.STEEL-GR 60	0.87	0.82	0.85	0.85
400.00	LF	STEEL PILING (HP 12X53)	58.62	55.70	57.25	57.19
26.00	LF	CORING DRILLED SHAFT	184.35	174.00	179.30	179.22
416.00	LF	DRILLED SHAFT (48" DIAMETER)	444.00	420.00	432.00	432.00
144.00	LF	PERMANENT STEEL CASING (48")	86.00	81.90	84.25	84.05
16.00	EACH	CROSSHOLE SONIC LOGGING (48" DI	1,775.00	1,680.00	1,728.00	1,727.67
26,890.00	LB	STR.ST.BM.SPANS(M270-GR50W)	5.50	5.25	5.40	5.38
64,350.00	CUIN	ELASTOMERIC BEARINGS	1.30	1.25	1.30	1.28
156.00	LF	ARM. JT W/NEOPRENE STRIP SEAL	155.00	147.00	151.20	151.07
1.00	EACH	BRIDGE NAME PLATE (TYPE D)	1,870.00	1,770.00	1,819.80	1,819.93
1,191.00	SQYD	FILTER BLANKET	10.00	3.70	3.80	5.83
596.00	CUYD	DUMPED RIPRAP	44.00	33.60	34.60	37.40
TOTAL AMOUNT BID FOR JOB			\$13,356,996.60	\$13,507,337.24	\$14,350,245.80	
TOTAL AMOUNT BID FOR BRIDGE			\$1,914,150.20	\$1,778,828.70	\$2,010,902.00	

BRIDGE ID	LENGTH	WIDTH	AREA (OUT-OUT)	NEW BRIDGE DESCRIPTION	EXISTING BRIDGE DESCRIPTION
07154	352.13	78.17	27,524.45	1A	1B
		A =	27,524.45		

1A 350'- PRESTRESSED CONC GIRDER (70,70,70,70,70') ON FOUR COL INT BENTS ON DRILLED SHAFTS AND STEEL PILE STUB END BENTS.

1B #00349 - 341.4' L X 31' W; CONSISTING OF 5-30' RCDG APPROACH SPANS SUPPORTED ON CONC COL BENTS AND 2-95' CONC DECK ARCH SPANS.

OUT TO OUT COST (\$/SF)=	\$1,914,150.20	/A =	\$69.54	* FHWA COST (\$/SF)=	\$1,820,016.20	/A =	\$66.12
LESS REMOVAL / TEMP. BR.	(\$/SF)	=	\$ 2.03	EXISTING BR. REMOVAL (\$/SF)	=	\$5.29	
NET COST (\$/SF)	=	\$67.51		* DEDUCT REMOVAL, TEMP. BR., RIPRAP, & FILTER BLANKET COSTS			

FUNCTION CLASS - MINOR ARTERIAL
 ON (06)

DESIGN SECTION - JGT