

STPR-0067(18)

ANALYSIS OF BIDS  
 JOB NO. FA6706 - BLAKES BRANCH STR. & APPRS. (S)  
 LETTING OF JULY 13, 2010

QUANTITY	UNIT	ITEM	WEST PLAINS BR. & GRADING, LLC	THOMPSON CONST., INC.	GEURIN CONTRACTORS, INC.	AVG. OF LOW BIDS
146.00	CUYD	UNCLASS.EXCAV.FOR STRS-BR	87.00	100.00	200.00	129.00
117.00	CUYD	CLASS S CONCRETE - BRIDGE	675.00	650.00	600.00	641.67
109.50	CUYD	CLASS S(AE) CONCRETE - BRIDGE	593.00	650.00	750.00	664.33
9.40	GAL	CLASS 1 PROTECT.SURF.TREATMENT	60.00	60.00	100.00	73.33
41,360.00	LB	REINF.STEEL-BRIDGE (GR 60)	0.90	0.90	1.00	0.93
66,080.00	LB	STR.ST.BM.SPANS(M270-GR50W)	1.52	1.85	2.00	1.79
3,753.00	CUIN	ELASTOMERIC BEARINGS	4.00	2.50	4.00	3.50
54.00	LF	SILICONE JOINT SEALANT	103.00	65.00	100.00	89.33
1.00	EACH	BRIDGE NAME PLATE (TYPE C)	500.00	300.00	200.00	333.33
676.00	SQYD	FILTER BLANKET	3.67	3.00	4.50	3.72
339.00	CUYD	DUMPED RIPRAP	38.00	45.00	60.00	47.67
TOTAL AMOUNT BID FOR JOB			\$678,042.87	\$692,995.20	\$778,311.50	
TOTAL AMOUNT BID FOR BRIDGE			\$331,277.02	\$352,336.50	\$399,979.00	

BRIDGE ID	LENGTH	WIDTH	AREA (OUT-OUT)	NEW BRIDGE DESCRIPTION	EXISTING BRIDGE DESCRIPTION
04914	132.12	27.17	3,589.40	1A	NA
		A =	3,589.40		

1A 130' - CONT COMP W-BEAM UNIT (40'-50'-40') ON TWO COL BENTS ON SPREAD FOOTINGS.

1B NA

OUT TO OUT COST (\$/SF)=	\$331,277.02	/A =	\$92.29	* FHWA COST (\$/SF)=	\$315,914.10	/A =	\$88.01
LESS REMOVAL / TEMP. BR.	(\$/SF)	=	NA	EXISTING BR. REMOVAL (\$/SF)	=	NA	
NET COST (\$/SF)	=	\$92.29		* DEDUCT REMOVAL, TEMP. BR., RIPRAP, & FILTER BLANKET COSTS			

FUNCTION CLASS - MAJOR COLLECTOR  
 ON (07)

DESIGN SECTION - JGT