

QUANTITY	UNIT	ITEM	GRAVES & ASSOCIATES, INC.	CHANCELLOR & SON, INC.	IDEAL CONSTRUCTION COMPANY	AVG. OF LOW BIDS
144.00	CUYD	UNCLASS.EXCAV.FOR STRS-BR	31.93	65.50	31.93	43.12
185.10	CUYD	CLASS S CONCRETE-BRIDGE	755.04	634.00	755.04	714.69
297.00	CUYD	CLASS S(AE) CONCRETE-BRIDGE	700.53	740.00	700.53	713.69
25.00	GAL	CLASS 1 PROTECT.SURF.TREATMENT	76.28	79.00	76.28	77.19
25,700.00	LB	REINF.STEEL-BRIDGE (GR 60)	0.84	1.06	1.66	1.19
65,710.00	LB	EPOXY COAT.REINF.STEEL-GR 60	1.10	1.16	1.10	1.12
1,570.00	LF	CONC.PILING (18" SQUARE)	80.08	90.00	80.08	83.39
170.00	LF	TEST PILE (18" SQUARE)	128.08	264.00	128.08	173.39
225,470.00	LB	STR.ST.PL.GRD.SPN(M270-GR50)	2.45	2.64	3.05	2.71
112.60	TON	PAINTING STRUCTURAL STEEL	551.40	792.00	551.40	631.60
15,218.80	CUIN	ELASTOMERIC BEARINGS	1.77	3.20	1.77	2.25
90.00	LF	PREFORMED JOINT SEAL	43.83	158.00	43.83	81.89
1.00	EACH	BRIDGE NAME PLATE (TYPE D)	631.80	528.00	631.80	597.20
32.00	CUYD	CONCRETE RIPRAP	485.00	610.00	485.00	526.67
TOTAL AMOUNT BID FOR JOB			\$32,180,377.50	\$32,800,094.88	\$33,567,223.05	
TOTAL AMOUNT BID FOR BRIDGE			\$1,257,211.35	\$1,405,574.16	\$1,413,567.35	

BRIDGE ID	LENGTH	WIDTH	AREA (OUT-OUT)	NEW BRIDGE DESCRIPTION	EXISTING BRIDGE DESCRIPTION
07117	235.26	43.17	10,155.42	1A	NA
		A =	10,155.42		

1A 233'- CONT COMP PLATE GIRDER UNIT (120'-113') ON MULTI-COL INT BENTS W/CONC FOUNDATION PILES & STUB END BENTS W/VERTICAL CONC PILES.

1B NA

OUT TO OUT COST (\$/SF)=	\$1,257,211.35	/A =	\$123.80	FHWA COST (\$/SF)=	\$1,241,691.35	/A =	\$122.27
LESS REMOVAL / TEMP. BR.	(\$/SF)	=	NA	EXISTING BR. REMOVAL (\$/SF)	=	NA	
NET COST (\$/SF)	=	\$123.80		DEDUCT REMOVAL, TEMP. BR., RIPRAP, FLTR BLNKT, SHORING & TRANS APP RAIL COSTS FROM FHWA COST.			

FUNCTION CLASS - 02 PRINCIPAL ARTERIAL - OTHER  
ON NHS

DESIGN SECTION - CRE