

ANALYSIS OF BIDS
 JOB NO. 110541 - BAYOU DEVIEW STR. & APPRS. (S)
 LETTING OF JANUARY 9, 2013

QUANTITY	UNIT	ITEM	ROBERTSON, INC BR. & GRADING DIV.	CHANCELOR & SON, INC.	ROBERTSON CONTRS., INC.	AVG OF LOW BIDS
1.00	L.S	REMV. EXIST. BR.STR. (SITE 1)	55,000.00	62,000.00	75,000.00	64,000.00
141.10	CUYD	CLASS S CONCRETE - BRIDGE	900.00	1,110.00	950.00	986.67
427.50	CUYD	CLASS S(AE) CONCRETE - BRIDGE	750.00	820.00	850.00	806.67
1,525.00	LF	PRESTRESSED CONC GRDS (TYPE III)	156.00	176.00	200.00	177.33
28.90	GAL	CLASS 1 PROTECT. SURF.TREATMENT	70.00	65.00	65.00	66.67
99,300.00	LB	REINF.STEEL-BRIDGE (GR 60)	0.89	1.10	1.10	1.03
870.00	LF	STEEL SHELL PILING (16" DIAMETER)	87.75	190.00	128.00	135.25
1,620.00	LF	STEEL SHELL PILING (24" DIAMETER)	132.25	257.00	155.00	181.42
237.00	LF	PILE ENCASEMENT	133.00	187.00	125.00	148.33
4,530.00	LB	STR.ST.BM.SPANS (M270-GR50W)	7.00	11.00	7.50	8.50
2,393.00	CUIN	ELASTOMERIC BEARINGS	7.45	8.50	8.50	8.15
74.00	LF	SILICONE JOINT SEALANT	73.00	38.00	70.00	60.33
1.00	EACH	BRIDGE NAME PLATE (TYPE D)	1,325.00	1,250.00	1,500.00	1,358.33
478.00	SQYD	FILTER BLANKET	3.00	2.00	5.00	3.33
270.00	CUYD	DUMPED RIPRAP	47.00	65.00	68.00	60.00
71.36	CUYD	APPROACH SLABS (TYPE SPECIAL)	370.00	500.00	500.00	456.67
33.80	CUYD	APPROACH GUTTERS (TYPE SPECIAL)	445.00	500.00	500.00	481.67
9892.00	LB	REINF.STEEL-RDWY (GR 60)	0.89	1.00	1.10	1.00

TOTAL AMOUNT BID FOR JOB \$2,764,333.20 \$3,113,217.85 \$3,658,650.25

TOTAL AMOUNT BID FOR BRIDGE **\$1,273,660.43** **\$1,729,849.00** **\$1,525,820.20**

BRIDGE ID	LENGTH	WIDTH	AREA (OUT-OUT)	NEW BRIDGE DESCRIPTION	EXISTING BRIDGE DESCRIPTION
07217	312.17	37.17	11,602.21	1A	1B
		A =	11,602.21		

1A 310' - CONT COMP PRESTRESSED CONC GIRDER UNIT TYPE III (5@ 62') ON CONC FILLED SHELL PILE BENTS.

1B M0849 - 304' L X 25.1' W; COMPRISED OF 16-19' CONC CHANNEL BEAMS SPANS SUPPORTED BY PILE BENTS.

OUT TO OUT COST (\$/SF) = \$1,273,660.43 /A = **\$109.78**
 LESS REMOVAL / TEMP. BR. (\$/SF) **\$4.74**

FHWA COST (\$/SF) = \$1,204,536.43. /A= \$103.82
 EXISTING BR. REMOVAL (\$/SF) = \$7.21

NET COST (\$/SF) **\$105.04**

DEDUCT REMVL, TEMP BR, RIPRAP, FLTR BLNKT, SHORING
 & TRANS APPR RAIL COSTS FROM FHWA COST.

FUNCTION CLASS - 06 MINOR ARTERIAL
 OFF NHS